

1231-1235 S Brand Blvd (Honda) - Los Angeles-South Coast County, Winter

EMFAC Off-Model Adjustment Factors for Gasoline Light Duty Vehicle to Account for the SAFE Vehicle Rule Applied**1231-1235 S Brand Blvd (Honda)
Los Angeles-South Coast County, Winter****1.0 Project Characteristics****1.1 Land Usage**

Land Uses	Size	Metric	Lot Acreage	Floor Surface Area	Population
Enclosed Parking with Elevator	12.57	1000sqft	0.29	12,574.00	0
Unenclosed Parking with Elevator	15.00	1000sqft	0.34	15,000.00	0
Automobile Care Center	41.38	1000sqft	1.00	20,245.00	0

1.2 Other Project Characteristics

Urbanization	Urban	Wind Speed (m/s)	2.2	Precipitation Freq (Days)	33
Climate Zone	12			Operational Year	2023
Utility Company	Glendale Water and Power				
CO2 Intensity (lb/MWhr)	948.98	CH4 Intensity (lb/MWhr)	0.033	N2O Intensity (lb/MWhr)	0.004

1.3 User Entered Comments & Non-Default Data

Project Characteristics - Land Use - 1.623 acres lot. 41,382 sf car center. 12,618 sf parking enclosed structure. 15,000 sf parking unenclosed structure.
Construction Phase - 20 demo, 2 prep, 4 grad, 200 bldg, 10 pave, 10 coat

Land Use - 70,718 SF (1.623 acres) site, 41,382 SF auto care (Service bays, sales office, parts storage, sales floor, advisor offices, cashiers), 12,574 SF enclosed parking with elevator and 15,000 SF of unenclosed parking on the roof.

Construction Phase - Construction Phase - 20 demo, 2 prep, 4 grad, 200 bldg, 10 pave, 10 coat

Grading - 675 CY grading

Demolition - Demo: 14,118 SF buildings

Architectural Coating - cc

Fleet Mix -

Area Coating -

1231-1235 S Brand Blvd (Honda) - Los Angeles-South Coast County, Winter

EMFAC Off-Model Adjustment Factors for Gasoline Light Duty Vehicle to Account for the SAFE Vehicle Rule Applied

Table Name	Column Name	Default Value	New Value
tblArchitecturalCoating	EF_Nonresidential_Exterior	100.00	250.00
tblArchitecturalCoating	EF_Nonresidential_Interior	100.00	250.00
tblArchitecturalCoating	EF_Residential_Exterior	50.00	100.00
tblGrading	MaterialExported	0.00	675.00
tblLandUse	LandUseSquareFeet	12,570.00	12,574.00
tblLandUse	LandUseSquareFeet	41,380.00	20,245.00
tblLandUse	LotAcreage	0.95	1.00

2.0 Emissions Summary

1231-1235 S Brand Blvd (Honda) - Los Angeles-South Coast County, Winter

EMFAC Off-Model Adjustment Factors for Gasoline Light Duty Vehicle to Account for the SAFE Vehicle Rule Applied**2.1 Overall Construction (Maximum Daily Emission)****Unmitigated Construction**

	ROG	NOx	CO	SO2	Fugitive PM10	Exhaust PM10	PM10 Total	Fugitive PM2.5	Exhaust PM2.5	PM2.5 Total	Bio- CO2	NBio- CO2	Total CO2	CH4	N2O	CO2e
Year	lb/day										lb/day					
2022	1.7517	19.9388	14.5584	0.0320	7.4876	0.8428	8.2515	3.5348	0.7876	4.2384	0.0000	3,234.629 2	3,234.629 2	0.7087	0.1837	3,307.076 0
2023	47.8910	12.0763	13.3333	0.0252	0.2524	0.5173	0.7697	0.0681	0.4994	0.5675	0.0000	2,334.944 7	2,334.944 7	0.4147	0.0275	2,351.896 8
Maximum	47.8910	19.9388	14.5584	0.0320	7.4876	0.8428	8.2515	3.5348	0.7876	4.2384	0.0000	3,234.629 2	3,234.629 2	0.7087	0.1837	3,307.076 0

Mitigated Construction

	ROG	NOx	CO	SO2	Fugitive PM10	Exhaust PM10	PM10 Total	Fugitive PM2.5	Exhaust PM2.5	PM2.5 Total	Bio- CO2	NBio- CO2	Total CO2	CH4	N2O	CO2e
Year	lb/day										lb/day					
2022	1.7517	19.9388	14.5584	0.0320	7.4876	0.8428	8.2515	3.5348	0.7876	4.2384	0.0000	3,234.629 2	3,234.629 2	0.7087	0.1837	3,307.076 0
2023	47.8910	12.0763	13.3333	0.0252	0.2524	0.5173	0.7697	0.0681	0.4994	0.5675	0.0000	2,334.944 7	2,334.944 7	0.4147	0.0275	2,351.896 8
Maximum	47.8910	19.9388	14.5584	0.0320	7.4876	0.8428	8.2515	3.5348	0.7876	4.2384	0.0000	3,234.629 2	3,234.629 2	0.7087	0.1837	3,307.076 0

EMFAC Off-Model Adjustment Factors for Gasoline Light Duty Vehicle to Account for the SAFE Vehicle Rule Applied

[illegible]

1231-1235 S Brand Blvd (Honda) - Los Angeles-South Coast County, Winter

EMFAC Off-Model Adjustment Factors for Gasoline Light Duty Vehicle to Account for the SAFE Vehicle Rule Applied**2.2 Overall Operational****Unmitigated Operational**

	ROG	NOx	CO	SO2	Fugitive PM10	Exhaust PM10	PM10 Total	Fugitive PM2.5	Exhaust PM2.5	PM2.5 Total	Bio- CO2	NBio- CO2	Total CO2	CH4	N2O	CO2e
Category	lb/day										lb/day					
Area	0.4648	6.0000e-005	7.0400e-003	0.0000		3.0000e-005	3.0000e-005		3.0000e-005	3.0000e-005		0.0151	0.0151	4.0000e-005		0.0161
Energy	0.0107	0.0977	0.0820	5.9000e-004		7.4200e-003	7.4200e-003		7.4200e-003	7.4200e-003		117.1959	117.1959	2.2500e-003	2.1500e-003	117.8923
Mobile	2.0181	1.7506	15.4121	0.0269	2.7679	0.0219	2.7897	0.7373	0.0203	0.7575		2,770.924 2	2,770.924 2	0.2616	0.1532	2,823.119 7
Total	2.4936	1.8483	15.5012	0.0275	2.7679	0.0293	2.7972	0.7373	0.0277	0.7650		2,888.135 1	2,888.135 1	0.2639	0.1554	2,941.028 1

Mitigated Operational

	ROG	NOx	CO	SO2	Fugitive PM10	Exhaust PM10	PM10 Total	Fugitive PM2.5	Exhaust PM2.5	PM2.5 Total	Bio- CO2	NBio- CO2	Total CO2	CH4	N2O	CO2e
Category	lb/day										lb/day					
Area	0.4648	6.0000e-005	7.0400e-003	0.0000		3.0000e-005	3.0000e-005		3.0000e-005	3.0000e-005		0.0151	0.0151	4.0000e-005		0.0161
Energy	0.0107	0.0977	0.0820	5.9000e-004		7.4200e-003	7.4200e-003		7.4200e-003	7.4200e-003		117.1959	117.1959	2.2500e-003	2.1500e-003	117.8923
Mobile	2.0181	1.7506	15.4121	0.0269	2.7679	0.0219	2.7897	0.7373	0.0203	0.7575		2,770.924 2	2,770.924 2	0.2616	0.1532	2,823.119 7
Total	2.4936	1.8483	15.5012	0.0275	2.7679	0.0293	2.7972	0.7373	0.0277	0.7650		2,888.135 1	2,888.135 1	0.2639	0.1554	2,941.028 1

1231-1235 S Brand Blvd (Honda) - Los Angeles-South Coast County, Winter

EMFAC Off-Model Adjustment Factors for Gasoline Light Duty Vehicle to Account for the SAFE Vehicle Rule Applied

	ROG	NOx	CO	SO2	Fugitive PM10	Exhaust PM10	PM10 Total	Fugitive PM2.5	Exhaust PM2.5	PM2.5 Total	Bio- CO2	NBio-CO2	Total CO2	CH4	N2O	CO2e
Percent Reduction	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00

3.0 Construction Detail**Construction Phase**

Phase Number	Phase Name	Phase Type	Start Date	End Date	Num Days Week	Num Days	Phase Description
1	Demolition	Demolition	11/1/2022	11/28/2022	5	20	
2	Site Preparation	Site Preparation	11/29/2022	11/30/2022	5	2	
3	Grading	Grading	12/1/2022	12/6/2022	5	4	
4	Building Construction	Building Construction	12/7/2022	9/12/2023	5	200	
5	Paving	Paving	9/13/2023	9/26/2023	5	10	
6	Architectural Coating	Architectural Coating	9/27/2023	10/10/2023	5	10	

Acres of Grading (Site Preparation Phase): 1.88**Acres of Grading (Grading Phase): 4****Acres of Paving: 0.63****Residential Indoor: 0; Residential Outdoor: 0; Non-Residential Indoor: 30,368; Non-Residential Outdoor: 10,123; Striped Parking Area: 1,654 (Architectural Coating – sqft)****OffRoad Equipment**

Phase Name	Offroad Equipment Type	Amount	Usage Hours	Horse Power	Load Factor
Architectural Coating	Air Compressors	1	6.00	78	0.48
Paving	Cement and Mortar Mixers	1	6.00	9	0.56
Demolition	Concrete/Industrial Saws	1	8.00	81	0.73
Building Construction	Cranes	1	6.00	231	0.29
Building Construction	Forklifts	1	6.00	89	0.20

1231-1235 S Brand Blvd (Honda) - Los Angeles-South Coast County, Winter

EMFAC Off-Model Adjustment Factors for Gasoline Light Duty Vehicle to Account for the SAFE Vehicle Rule Applied

Building Construction	Generator Sets	1	8.00	84	0.74
Grading	Graders	1	8.00	187	0.41
Site Preparation	Graders	1	8.00	187	0.41
Paving	Pavers	1	6.00	130	0.42
Paving	Paving Equipment	1	8.00	132	0.36
Paving	Rollers	1	7.00	80	0.38
Demolition	Rubber Tired Dozers	1	8.00	247	0.40
Grading	Rubber Tired Dozers	1	8.00	247	0.40
Site Preparation	Rubber Tired Dozers	1	7.00	247	0.40
Building Construction	Tractors/Loaders/Backhoes	1	6.00	97	0.37
Demolition	Tractors/Loaders/Backhoes	3	8.00	97	0.37
Grading	Tractors/Loaders/Backhoes	2	7.00	97	0.37
Paving	Tractors/Loaders/Backhoes	1	8.00	97	0.37
Site Preparation	Tractors/Loaders/Backhoes	1	8.00	97	0.37
Building Construction	Welders	3	8.00	46	0.45

Trips and VMT

Phase Name	Offroad Equipment Count	Worker Trip Number	Vendor Trip Number	Hauling Trip Number	Worker Trip Length	Vendor Trip Length	Hauling Trip Length	Worker Vehicle Class	Vendor Vehicle Class	Hauling Vehicle Class
Architectural Coating	1	4.00	0.00	0.00	14.70	6.90	20.00	LD_Mix	HDT_Mix	HHDT
Building Construction	7	18.00	8.00	0.00	14.70	6.90	20.00	LD_Mix	HDT_Mix	HHDT
Demolition	5	13.00	0.00	64.00	14.70	6.90	20.00	LD_Mix	HDT_Mix	HHDT
Grading	4	10.00	0.00	67.00	14.70	6.90	20.00	LD_Mix	HDT_Mix	HHDT
Paving	5	13.00	0.00	0.00	14.70	6.90	20.00	LD_Mix	HDT_Mix	HHDT
Site Preparation	3	8.00	0.00	0.00	14.70	6.90	20.00	LD_Mix	HDT_Mix	HHDT

3.1 Mitigation Measures Construction

1231-1235 S Brand Blvd (Honda) - Los Angeles-South Coast County, Winter

EMFAC Off-Model Adjustment Factors for Gasoline Light Duty Vehicle to Account for the SAFE Vehicle Rule Applied**3.2 Demolition - 2022****Unmitigated Construction On-Site**

	ROG	NOx	CO	SO2	Fugitive PM10	Exhaust PM10	PM10 Total	Fugitive PM2.5	Exhaust PM2.5	PM2.5 Total	Bio- CO2	NBio- CO2	Total CO2	CH4	N2O	CO2e
Category	lb/day										lb/day					
Fugitive Dust					0.6949	0.0000	0.6949	0.1052	0.0000	0.1052			0.0000			0.0000
Off-Road	1.6889	16.6217	13.9605	0.0241		0.8379	0.8379		0.7829	0.7829		2,323.4168	2,323.4168	0.5921		2,338.2191
Total	1.6889	16.6217	13.9605	0.0241	0.6949	0.8379	1.5328	0.1052	0.7829	0.8881		2,323.4168	2,323.4168	0.5921		2,338.2191

Unmitigated Construction Off-Site

	ROG	NOx	CO	SO2	Fugitive PM10	Exhaust PM10	PM10 Total	Fugitive PM2.5	Exhaust PM2.5	PM2.5 Total	Bio- CO2	NBio- CO2	Total CO2	CH4	N2O	CO2e
Category	lb/day										lb/day					
Hauling	0.0146	0.5593	0.1275	1.9900e-003	0.0560	4.0000e-003	0.0600	0.0154	3.8300e-003	0.0192		217.9121	217.9121	0.0116	0.0346	228.5044
Vendor	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000		0.0000	0.0000	0.0000	0.0000	0.0000
Worker	0.0482	0.0363	0.4704	1.2600e-003	0.1453	9.3000e-004	0.1462	0.0385	8.6000e-004	0.0394		128.0673	128.0673	3.7000e-003	3.4800e-003	129.1958
Total	0.0627	0.5956	0.5980	3.2500e-003	0.2013	4.9300e-003	0.2063	0.0539	4.6900e-003	0.0586		345.9794	345.9794	0.0153	0.0381	357.7002

1231-1235 S Brand Blvd (Honda) - Los Angeles-South Coast County, Winter

EMFAC Off-Model Adjustment Factors for Gasoline Light Duty Vehicle to Account for the SAFE Vehicle Rule Applied**3.2 Demolition - 2022****Mitigated Construction On-Site**

	ROG	NOx	CO	SO2	Fugitive PM10	Exhaust PM10	PM10 Total	Fugitive PM2.5	Exhaust PM2.5	PM2.5 Total	Bio- CO2	NBio- CO2	Total CO2	CH4	N2O	CO2e
Category	lb/day										lb/day					
Fugitive Dust					0.6949	0.0000	0.6949	0.1052	0.0000	0.1052			0.0000			0.0000
Off-Road	1.6889	16.6217	13.9605	0.0241		0.8379	0.8379		0.7829	0.7829	0.0000	2,323.4168	2,323.4168	0.5921		2,338.2191
Total	1.6889	16.6217	13.9605	0.0241	0.6949	0.8379	1.5328	0.1052	0.7829	0.8881	0.0000	2,323.4168	2,323.4168	0.5921		2,338.2191

Mitigated Construction Off-Site

	ROG	NOx	CO	SO2	Fugitive PM10	Exhaust PM10	PM10 Total	Fugitive PM2.5	Exhaust PM2.5	PM2.5 Total	Bio- CO2	NBio- CO2	Total CO2	CH4	N2O	CO2e
Category	lb/day										lb/day					
Hauling	0.0146	0.5593	0.1275	1.9900e-003	0.0560	4.0000e-003	0.0600	0.0154	3.8300e-003	0.0192		217.9121	217.9121	0.0116	0.0346	228.5044
Vendor	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000		0.0000	0.0000	0.0000	0.0000	0.0000
Worker	0.0482	0.0363	0.4704	1.2600e-003	0.1453	9.3000e-004	0.1462	0.0385	8.6000e-004	0.0394		128.0673	128.0673	3.7000e-003	3.4800e-003	129.1958
Total	0.0627	0.5956	0.5980	3.2500e-003	0.2013	4.9300e-003	0.2063	0.0539	4.6900e-003	0.0586		345.9794	345.9794	0.0153	0.0381	357.7002

1231-1235 S Brand Blvd (Honda) - Los Angeles-South Coast County, Winter

EMFAC Off-Model Adjustment Factors for Gasoline Light Duty Vehicle to Account for the SAFE Vehicle Rule Applied**3.3 Site Preparation - 2022****Unmitigated Construction On-Site**

	ROG	NOx	CO	SO2	Fugitive PM10	Exhaust PM10	PM10 Total	Fugitive PM2.5	Exhaust PM2.5	PM2.5 Total	Bio- CO2	NBio- CO2	Total CO2	CH4	N2O	CO2e
Category	lb/day										lb/day					
Fugitive Dust					6.2662	0.0000	6.2662	3.0041	0.0000	3.0041			0.0000			0.0000
Off-Road	1.3122	14.6277	7.0939	0.0172		0.6225	0.6225		0.5727	0.5727		1,666.173 8	1,666.173 8	0.5389		1,679.645 7
Total	1.3122	14.6277	7.0939	0.0172	6.2662	0.6225	6.8887	3.0041	0.5727	3.5768		1,666.173 8	1,666.173 8	0.5389		1,679.645 7

Unmitigated Construction Off-Site

	ROG	NOx	CO	SO2	Fugitive PM10	Exhaust PM10	PM10 Total	Fugitive PM2.5	Exhaust PM2.5	PM2.5 Total	Bio- CO2	NBio- CO2	Total CO2	CH4	N2O	CO2e
Category	lb/day										lb/day					
Hauling	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000		0.0000	0.0000	0.0000	0.0000	0.0000
Vendor	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000		0.0000	0.0000	0.0000	0.0000	0.0000
Worker	0.0296	0.0223	0.2895	7.7000e-004	0.0894	5.7000e-004	0.0900	0.0237	5.3000e-004	0.0242		78.8107	78.8107	2.2800e-003	2.1400e-003	79.5051
Total	0.0296	0.0223	0.2895	7.7000e-004	0.0894	5.7000e-004	0.0900	0.0237	5.3000e-004	0.0242		78.8107	78.8107	2.2800e-003	2.1400e-003	79.5051

1231-1235 S Brand Blvd (Honda) - Los Angeles-South Coast County, Winter

EMFAC Off-Model Adjustment Factors for Gasoline Light Duty Vehicle to Account for the SAFE Vehicle Rule Applied**3.3 Site Preparation - 2022****Mitigated Construction On-Site**

	ROG	NOx	CO	SO2	Fugitive PM10	Exhaust PM10	PM10 Total	Fugitive PM2.5	Exhaust PM2.5	PM2.5 Total	Bio- CO2	NBio- CO2	Total CO2	CH4	N2O	CO2e
Category	lb/day										lb/day					
Fugitive Dust					6.2662	0.0000	6.2662	3.0041	0.0000	3.0041			0.0000			0.0000
Off-Road	1.3122	14.6277	7.0939	0.0172		0.6225	0.6225		0.5727	0.5727	0.0000	1,666.173 8	1,666.173 8	0.5389		1,679.645 7
Total	1.3122	14.6277	7.0939	0.0172	6.2662	0.6225	6.8887	3.0041	0.5727	3.5768	0.0000	1,666.173 8	1,666.173 8	0.5389		1,679.645 7

Mitigated Construction Off-Site

	ROG	NOx	CO	SO2	Fugitive PM10	Exhaust PM10	PM10 Total	Fugitive PM2.5	Exhaust PM2.5	PM2.5 Total	Bio- CO2	NBio- CO2	Total CO2	CH4	N2O	CO2e
Category	lb/day										lb/day					
Hauling	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000		0.0000	0.0000	0.0000	0.0000	0.0000
Vendor	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000		0.0000	0.0000	0.0000	0.0000	0.0000
Worker	0.0296	0.0223	0.2895	7.7000e-004	0.0894	5.7000e-004	0.0900	0.0237	5.3000e-004	0.0242		78.8107	78.8107	2.2800e-003	2.1400e-003	79.5051
Total	0.0296	0.0223	0.2895	7.7000e-004	0.0894	5.7000e-004	0.0900	0.0237	5.3000e-004	0.0242		78.8107	78.8107	2.2800e-003	2.1400e-003	79.5051

1231-1235 S Brand Blvd (Honda) - Los Angeles-South Coast County, Winter

EMFAC Off-Model Adjustment Factors for Gasoline Light Duty Vehicle to Account for the SAFE Vehicle Rule Applied**3.4 Grading - 2022****Unmitigated Construction On-Site**

	ROG	NOx	CO	SO2	Fugitive PM10	Exhaust PM10	PM10 Total	Fugitive PM2.5	Exhaust PM2.5	PM2.5 Total	Bio- CO2	NBio- CO2	Total CO2	CH4	N2O	CO2e
Category	lb/day										lb/day					
Fugitive Dust					7.0826	0.0000	7.0826	3.4247	0.0000	3.4247			0.0000			0.0000
Off-Road	1.5403	16.9836	9.2202	0.0206		0.7423	0.7423		0.6829	0.6829		1,995.4825	1,995.4825	0.6454		2,011.6169
Total	1.5403	16.9836	9.2202	0.0206	7.0826	0.7423	7.8249	3.4247	0.6829	4.1076		1,995.4825	1,995.4825	0.6454		2,011.6169

Unmitigated Construction Off-Site

	ROG	NOx	CO	SO2	Fugitive PM10	Exhaust PM10	PM10 Total	Fugitive PM2.5	Exhaust PM2.5	PM2.5 Total	Bio- CO2	NBio- CO2	Total CO2	CH4	N2O	CO2e
Category	lb/day										lb/day					
Hauling	0.0762	2.9273	0.6675	0.0104	0.2932	0.0209	0.3141	0.0804	0.0200	0.1004		1,140.6334	1,140.6334	0.0605	0.1810	1,196.0777
Vendor	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000		0.0000	0.0000	0.0000	0.0000	0.0000
Worker	0.0371	0.0279	0.3619	9.7000e-004	0.1118	7.2000e-004	0.1125	0.0296	6.6000e-004	0.0303		98.5133	98.5133	2.8500e-003	2.6700e-003	99.3813
Total	0.1132	2.9552	1.0293	0.0114	0.4050	0.0217	0.4266	0.1100	0.0207	0.1307		1,239.1467	1,239.1467	0.0633	0.1837	1,295.4591

1231-1235 S Brand Blvd (Honda) - Los Angeles-South Coast County, Winter

EMFAC Off-Model Adjustment Factors for Gasoline Light Duty Vehicle to Account for the SAFE Vehicle Rule Applied**3.4 Grading - 2022****Mitigated Construction On-Site**

	ROG	NOx	CO	SO2	Fugitive PM10	Exhaust PM10	PM10 Total	Fugitive PM2.5	Exhaust PM2.5	PM2.5 Total	Bio- CO2	NBio- CO2	Total CO2	CH4	N2O	CO2e
Category	lb/day										lb/day					
Fugitive Dust					7.0826	0.0000	7.0826	3.4247	0.0000	3.4247			0.0000			0.0000
Off-Road	1.5403	16.9836	9.2202	0.0206		0.7423	0.7423		0.6829	0.6829	0.0000	1,995.4825	1,995.4825	0.6454		2,011.6169
Total	1.5403	16.9836	9.2202	0.0206	7.0826	0.7423	7.8249	3.4247	0.6829	4.1076	0.0000	1,995.4825	1,995.4825	0.6454		2,011.6169

Mitigated Construction Off-Site

	ROG	NOx	CO	SO2	Fugitive PM10	Exhaust PM10	PM10 Total	Fugitive PM2.5	Exhaust PM2.5	PM2.5 Total	Bio- CO2	NBio- CO2	Total CO2	CH4	N2O	CO2e
Category	lb/day										lb/day					
Hauling	0.0762	2.9273	0.6675	0.0104	0.2932	0.0209	0.3141	0.0804	0.0200	0.1004		1,140.6334	1,140.6334	0.0605	0.1810	1,196.0777
Vendor	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000		0.0000	0.0000	0.0000	0.0000	0.0000
Worker	0.0371	0.0279	0.3619	9.7000e-004	0.1118	7.2000e-004	0.1125	0.0296	6.6000e-004	0.0303		98.5133	98.5133	2.8500e-003	2.6700e-003	99.3813
Total	0.1132	2.9552	1.0293	0.0114	0.4050	0.0217	0.4266	0.1100	0.0207	0.1307		1,239.1467	1,239.1467	0.0633	0.1837	1,295.4591

1231-1235 S Brand Blvd (Honda) - Los Angeles-South Coast County, Winter

EMFAC Off-Model Adjustment Factors for Gasoline Light Duty Vehicle to Account for the SAFE Vehicle Rule Applied**3.5 Building Construction - 2022****Unmitigated Construction On-Site**

	ROG	NOx	CO	SO2	Fugitive PM10	Exhaust PM10	PM10 Total	Fugitive PM2.5	Exhaust PM2.5	PM2.5 Total	Bio- CO2	NBio- CO2	Total CO2	CH4	N2O	CO2e
Category	lb/day										lb/day					
Off-Road	1.6487	12.5031	12.7264	0.0221		0.5889	0.5889		0.5689	0.5689		2,001.5429	2,001.5429	0.3486		2,010.2581
Total	1.6487	12.5031	12.7264	0.0221		0.5889	0.5889		0.5689	0.5689		2,001.5429	2,001.5429	0.3486		2,010.2581

Unmitigated Construction Off-Site

	ROG	NOx	CO	SO2	Fugitive PM10	Exhaust PM10	PM10 Total	Fugitive PM2.5	Exhaust PM2.5	PM2.5 Total	Bio- CO2	NBio- CO2	Total CO2	CH4	N2O	CO2e
Category	lb/day										lb/day					
Hauling	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000		0.0000	0.0000	0.0000	0.0000	0.0000
Vendor	0.0156	0.4080	0.1390	1.5700e-003	0.0512	3.7500e-003	0.0550	0.0148	3.5800e-003	0.0183		168.4325	168.4325	5.6100e-003	0.0243	175.8122
Worker	0.0667	0.0503	0.6514	1.7400e-003	0.2012	1.2900e-003	0.2025	0.0534	1.1900e-003	0.0546		177.3240	177.3240	5.1300e-003	4.8100e-003	178.8864
Total	0.0822	0.4583	0.7904	3.3100e-003	0.2524	5.0400e-003	0.2575	0.0681	4.7700e-003	0.0729		345.7565	345.7565	0.0107	0.0291	354.6987

1231-1235 S Brand Blvd (Honda) - Los Angeles-South Coast County, Winter

EMFAC Off-Model Adjustment Factors for Gasoline Light Duty Vehicle to Account for the SAFE Vehicle Rule Applied**3.5 Building Construction - 2022****Mitigated Construction On-Site**

	ROG	NOx	CO	SO2	Fugitive PM10	Exhaust PM10	PM10 Total	Fugitive PM2.5	Exhaust PM2.5	PM2.5 Total	Bio- CO2	NBio- CO2	Total CO2	CH4	N2O	CO2e
Category	lb/day										lb/day					
Off-Road	1.6487	12.5031	12.7264	0.0221		0.5889	0.5889		0.5689	0.5689	0.0000	2,001.5429	2,001.5429	0.3486		2,010.2581
Total	1.6487	12.5031	12.7264	0.0221		0.5889	0.5889		0.5689	0.5689	0.0000	2,001.5429	2,001.5429	0.3486		2,010.2581

Mitigated Construction Off-Site

	ROG	NOx	CO	SO2	Fugitive PM10	Exhaust PM10	PM10 Total	Fugitive PM2.5	Exhaust PM2.5	PM2.5 Total	Bio- CO2	NBio- CO2	Total CO2	CH4	N2O	CO2e
Category	lb/day										lb/day					
Hauling	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000		0.0000	0.0000	0.0000	0.0000	0.0000
Vendor	0.0156	0.4080	0.1390	1.5700e-003	0.0512	3.7500e-003	0.0550	0.0148	3.5800e-003	0.0183		168.4325	168.4325	5.6100e-003	0.0243	175.8122
Worker	0.0667	0.0503	0.6514	1.7400e-003	0.2012	1.2900e-003	0.2025	0.0534	1.1900e-003	0.0546		177.3240	177.3240	5.1300e-003	4.8100e-003	178.8864
Total	0.0822	0.4583	0.7904	3.3100e-003	0.2524	5.0400e-003	0.2575	0.0681	4.7700e-003	0.0729		345.7565	345.7565	0.0107	0.0291	354.6987

1231-1235 S Brand Blvd (Honda) - Los Angeles-South Coast County, Winter

EMFAC Off-Model Adjustment Factors for Gasoline Light Duty Vehicle to Account for the SAFE Vehicle Rule Applied**3.5 Building Construction - 2023****Unmitigated Construction On-Site**

	ROG	NOx	CO	SO2	Fugitive PM10	Exhaust PM10	PM10 Total	Fugitive PM2.5	Exhaust PM2.5	PM2.5 Total	Bio- CO2	NBio- CO2	Total CO2	CH4	N2O	CO2e
Category	lb/day										lb/day					
Off-Road	1.5233	11.7104	12.6111	0.0221		0.5145	0.5145		0.4968	0.4968		2,001.7877	2,001.7877	0.3399		2,010.2858
Total	1.5233	11.7104	12.6111	0.0221		0.5145	0.5145		0.4968	0.4968		2,001.7877	2,001.7877	0.3399		2,010.2858

Unmitigated Construction Off-Site

	ROG	NOx	CO	SO2	Fugitive PM10	Exhaust PM10	PM10 Total	Fugitive PM2.5	Exhaust PM2.5	PM2.5 Total	Bio- CO2	NBio- CO2	Total CO2	CH4	N2O	CO2e
Category	lb/day										lb/day					
Hauling	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000		0.0000	0.0000	0.0000	0.0000	0.0000
Vendor	8.8900e-003	0.3215	0.1227	1.4900e-003	0.0512	1.5500e-003	0.0528	0.0148	1.4900e-003	0.0162		160.4962	160.4962	5.3500e-003	0.0231	167.5129
Worker	0.0619	0.0444	0.5996	1.6900e-003	0.2012	1.2100e-003	0.2024	0.0534	1.1200e-003	0.0545		172.6608	172.6608	4.6000e-003	4.4400e-003	174.0982
Total	0.0708	0.3659	0.7223	3.1800e-003	0.2524	2.7600e-003	0.2552	0.0681	2.6100e-003	0.0707		333.1571	333.1571	9.9500e-003	0.0275	341.6111

1231-1235 S Brand Blvd (Honda) - Los Angeles-South Coast County, Winter

EMFAC Off-Model Adjustment Factors for Gasoline Light Duty Vehicle to Account for the SAFE Vehicle Rule Applied**3.5 Building Construction - 2023****Mitigated Construction On-Site**

	ROG	NOx	CO	SO2	Fugitive PM10	Exhaust PM10	PM10 Total	Fugitive PM2.5	Exhaust PM2.5	PM2.5 Total	Bio- CO2	NBio- CO2	Total CO2	CH4	N2O	CO2e
Category	lb/day										lb/day					
Off-Road	1.5233	11.7104	12.6111	0.0221		0.5145	0.5145		0.4968	0.4968	0.0000	2,001.7877	2,001.7877	0.3399		2,010.2858
Total	1.5233	11.7104	12.6111	0.0221		0.5145	0.5145		0.4968	0.4968	0.0000	2,001.7877	2,001.7877	0.3399		2,010.2858

Mitigated Construction Off-Site

	ROG	NOx	CO	SO2	Fugitive PM10	Exhaust PM10	PM10 Total	Fugitive PM2.5	Exhaust PM2.5	PM2.5 Total	Bio- CO2	NBio- CO2	Total CO2	CH4	N2O	CO2e
Category	lb/day										lb/day					
Hauling	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000		0.0000	0.0000	0.0000	0.0000	0.0000
Vendor	8.8900e-003	0.3215	0.1227	1.4900e-003	0.0512	1.5500e-003	0.0528	0.0148	1.4900e-003	0.0162		160.4962	160.4962	5.3500e-003	0.0231	167.5129
Worker	0.0619	0.0444	0.5996	1.6900e-003	0.2012	1.2100e-003	0.2024	0.0534	1.1200e-003	0.0545		172.6608	172.6608	4.6000e-003	4.4400e-003	174.0982
Total	0.0708	0.3659	0.7223	3.1800e-003	0.2524	2.7600e-003	0.2552	0.0681	2.6100e-003	0.0707		333.1571	333.1571	9.9500e-003	0.0275	341.6111

1231-1235 S Brand Blvd (Honda) - Los Angeles-South Coast County, Winter

EMFAC Off-Model Adjustment Factors for Gasoline Light Duty Vehicle to Account for the SAFE Vehicle Rule Applied**3.6 Paving - 2023****Unmitigated Construction On-Site**

	ROG	NOx	CO	SO2	Fugitive PM10	Exhaust PM10	PM10 Total	Fugitive PM2.5	Exhaust PM2.5	PM2.5 Total	Bio- CO2	NBio- CO2	Total CO2	CH4	N2O	CO2e
Category	lb/day										lb/day					
Off-Road	0.6446	6.2357	8.8024	0.0136		0.3084	0.3084		0.2846	0.2846		1,297.688 0	1,297.688 0	0.4114		1,307.972 5
Paving	0.0000					0.0000	0.0000		0.0000	0.0000			0.0000			0.0000
Total	0.6446	6.2357	8.8024	0.0136		0.3084	0.3084		0.2846	0.2846		1,297.688 0	1,297.688 0	0.4114		1,307.972 5

Unmitigated Construction Off-Site

	ROG	NOx	CO	SO2	Fugitive PM10	Exhaust PM10	PM10 Total	Fugitive PM2.5	Exhaust PM2.5	PM2.5 Total	Bio- CO2	NBio- CO2	Total CO2	CH4	N2O	CO2e
Category	lb/day										lb/day					
Hauling	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000		0.0000	0.0000	0.0000	0.0000	0.0000
Vendor	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000		0.0000	0.0000	0.0000	0.0000	0.0000
Worker	0.0447	0.0321	0.4330	1.2200e-003	0.1453	8.8000e-004	0.1462	0.0385	8.1000e-004	0.0393		124.6995	124.6995	3.3200e-003	3.2000e-003	125.7376
Total	0.0447	0.0321	0.4330	1.2200e-003	0.1453	8.8000e-004	0.1462	0.0385	8.1000e-004	0.0393		124.6995	124.6995	3.3200e-003	3.2000e-003	125.7376

1231-1235 S Brand Blvd (Honda) - Los Angeles-South Coast County, Winter

EMFAC Off-Model Adjustment Factors for Gasoline Light Duty Vehicle to Account for the SAFE Vehicle Rule Applied**3.6 Paving - 2023****Mitigated Construction On-Site**

	ROG	NOx	CO	SO2	Fugitive PM10	Exhaust PM10	PM10 Total	Fugitive PM2.5	Exhaust PM2.5	PM2.5 Total	Bio- CO2	NBio- CO2	Total CO2	CH4	N2O	CO2e
Category	lb/day										lb/day					
Off-Road	0.6446	6.2357	8.8024	0.0136		0.3084	0.3084		0.2846	0.2846	0.0000	1,297.688 0	1,297.688 0	0.4114		1,307.972 5
Paving	0.0000					0.0000	0.0000		0.0000	0.0000			0.0000			0.0000
Total	0.6446	6.2357	8.8024	0.0136		0.3084	0.3084		0.2846	0.2846	0.0000	1,297.688 0	1,297.688 0	0.4114		1,307.972 5

Mitigated Construction Off-Site

	ROG	NOx	CO	SO2	Fugitive PM10	Exhaust PM10	PM10 Total	Fugitive PM2.5	Exhaust PM2.5	PM2.5 Total	Bio- CO2	NBio- CO2	Total CO2	CH4	N2O	CO2e
Category	lb/day										lb/day					
Hauling	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000		0.0000	0.0000	0.0000	0.0000	0.0000
Vendor	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000		0.0000	0.0000	0.0000	0.0000	0.0000
Worker	0.0447	0.0321	0.4330	1.2200e-003	0.1453	8.8000e-004	0.1462	0.0385	8.1000e-004	0.0393		124.6995	124.6995	3.3200e-003	3.2000e-003	125.7376
Total	0.0447	0.0321	0.4330	1.2200e-003	0.1453	8.8000e-004	0.1462	0.0385	8.1000e-004	0.0393		124.6995	124.6995	3.3200e-003	3.2000e-003	125.7376

1231-1235 S Brand Blvd (Honda) - Los Angeles-South Coast County, Winter

EMFAC Off-Model Adjustment Factors for Gasoline Light Duty Vehicle to Account for the SAFE Vehicle Rule Applied**3.7 Architectural Coating - 2023****Unmitigated Construction On-Site**

	ROG	NOx	CO	SO2	Fugitive PM10	Exhaust PM10	PM10 Total	Fugitive PM2.5	Exhaust PM2.5	PM2.5 Total	Bio- CO2	NBio- CO2	Total CO2	CH4	N2O	CO2e
Category	lb/day										lb/day					
Archit. Coating	47.6856					0.0000	0.0000		0.0000	0.0000			0.0000			0.0000
Off-Road	0.1917	1.3030	1.8111	2.9700e-003		0.0708	0.0708		0.0708	0.0708		281.4481	281.4481	0.0168		281.8690
Total	47.8772	1.3030	1.8111	2.9700e-003		0.0708	0.0708		0.0708	0.0708		281.4481	281.4481	0.0168		281.8690

Unmitigated Construction Off-Site

	ROG	NOx	CO	SO2	Fugitive PM10	Exhaust PM10	PM10 Total	Fugitive PM2.5	Exhaust PM2.5	PM2.5 Total	Bio- CO2	NBio- CO2	Total CO2	CH4	N2O	CO2e
Category	lb/day										lb/day					
Hauling	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000		0.0000	0.0000	0.0000	0.0000	0.0000
Vendor	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000		0.0000	0.0000	0.0000	0.0000	0.0000
Worker	0.0138	9.8600e-003	0.1332	3.7000e-004	0.0447	2.7000e-004	0.0450	0.0119	2.5000e-004	0.0121		38.3691	38.3691	1.0200e-003	9.9000e-004	38.6885
Total	0.0138	9.8600e-003	0.1332	3.7000e-004	0.0447	2.7000e-004	0.0450	0.0119	2.5000e-004	0.0121		38.3691	38.3691	1.0200e-003	9.9000e-004	38.6885

1231-1235 S Brand Blvd (Honda) - Los Angeles-South Coast County, Winter

EMFAC Off-Model Adjustment Factors for Gasoline Light Duty Vehicle to Account for the SAFE Vehicle Rule Applied**3.7 Architectural Coating - 2023****Mitigated Construction On-Site**

	ROG	NOx	CO	SO2	Fugitive PM10	Exhaust PM10	PM10 Total	Fugitive PM2.5	Exhaust PM2.5	PM2.5 Total	Bio- CO2	NBio- CO2	Total CO2	CH4	N2O	CO2e
Category	lb/day										lb/day					
Archit. Coating	47.6856					0.0000	0.0000		0.0000	0.0000			0.0000			0.0000
Off-Road	0.1917	1.3030	1.8111	2.9700e-003		0.0708	0.0708		0.0708	0.0708	0.0000	281.4481	281.4481	0.0168		281.8690
Total	47.8772	1.3030	1.8111	2.9700e-003		0.0708	0.0708		0.0708	0.0708	0.0000	281.4481	281.4481	0.0168		281.8690

Mitigated Construction Off-Site

	ROG	NOx	CO	SO2	Fugitive PM10	Exhaust PM10	PM10 Total	Fugitive PM2.5	Exhaust PM2.5	PM2.5 Total	Bio- CO2	NBio- CO2	Total CO2	CH4	N2O	CO2e
Category	lb/day										lb/day					
Hauling	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000		0.0000	0.0000	0.0000	0.0000	0.0000
Vendor	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000		0.0000	0.0000	0.0000	0.0000	0.0000
Worker	0.0138	9.8600e-003	0.1332	3.7000e-004	0.0447	2.7000e-004	0.0450	0.0119	2.5000e-004	0.0121		38.3691	38.3691	1.0200e-003	9.9000e-004	38.6885
Total	0.0138	9.8600e-003	0.1332	3.7000e-004	0.0447	2.7000e-004	0.0450	0.0119	2.5000e-004	0.0121		38.3691	38.3691	1.0200e-003	9.9000e-004	38.6885

1231-1235 S Brand Blvd (Honda) - Los Angeles-South Coast County, Winter

EMFAC Off-Model Adjustment Factors for Gasoline Light Duty Vehicle to Account for the SAFE Vehicle Rule Applied**4.0 Operational Detail - Mobile****4.1 Mitigation Measures Mobile**

	ROG	NOx	CO	SO2	Fugitive PM10	Exhaust PM10	PM10 Total	Fugitive PM2.5	Exhaust PM2.5	PM2.5 Total	Bio- CO2	NBio- CO2	Total CO2	CH4	N2O	CO2e
Category	lb/day										lb/day					
Mitigated	2.0181	1.7506	15.4121	0.0269	2.7679	0.0219	2.7897	0.7373	0.0203	0.7575		2,770.924 2	2,770.924 2	0.2616	0.1532	2,823.119 7
Unmitigated	2.0181	1.7506	15.4121	0.0269	2.7679	0.0219	2.7897	0.7373	0.0203	0.7575		2,770.924 2	2,770.924 2	0.2616	0.1532	2,823.119 7

4.2 Trip Summary Information

	Average Daily Trip Rate			Unmitigated	Mitigated
Land Use	Weekday	Saturday	Sunday	Annual VMT	Annual VMT
Automobile Care Center	981.53	981.53	491.59	1,221,058	1,221,058
Enclosed Parking with Elevator	0.00	0.00	0.00		
Unenclosed Parking with Elevator	0.00	0.00	0.00		
Total	981.53	981.53	491.59	1,221,058	1,221,058

4.3 Trip Type Information

	Miles			Trip %			Trip Purpose %		
Land Use	H-W or C-W	H-S or C-C	H-O or C-NW	H-W or C-W	H-S or C-C	H-O or C-NW	Primary	Diverted	Pass-by
Automobile Care Center	16.60	8.40	6.90	33.00	48.00	19.00	21	51	28
Enclosed Parking with Elevator	16.60	8.40	6.90	0.00	0.00	0.00	0	0	0
Unenclosed Parking with	16.60	8.40	6.90	0.00	0.00	0.00	0	0	0

1231-1235 S Brand Blvd (Honda) - Los Angeles-South Coast County, Winter

EMFAC Off-Model Adjustment Factors for Gasoline Light Duty Vehicle to Account for the SAFE Vehicle Rule Applied**4.4 Fleet Mix**

Land Use	LDA	LDT1	LDT2	MDV	LHD1	LHD2	MHD	HHD	OBUS	UBUS	MCY	SBUS	MH
Automobile Care Center	0.544785	0.062844	0.187478	0.127235	0.023089	0.006083	0.010475	0.008012	0.000925	0.000611	0.024394	0.000698	0.003374
Enclosed Parking with Elevator	0.544785	0.062844	0.187478	0.127235	0.023089	0.006083	0.010475	0.008012	0.000925	0.000611	0.024394	0.000698	0.003374
Unenclosed Parking with Elevator	0.544785	0.062844	0.187478	0.127235	0.023089	0.006083	0.010475	0.008012	0.000925	0.000611	0.024394	0.000698	0.003374

5.0 Energy Detail

Historical Energy Use: N

5.1 Mitigation Measures Energy

	ROG	NOx	CO	SO2	Fugitive PM10	Exhaust PM10	PM10 Total	Fugitive PM2.5	Exhaust PM2.5	PM2.5 Total	Bio- CO2	NBio- CO2	Total CO2	CH4	N2O	CO2e
Category	lb/day										lb/day					
NaturalGas Mitigated	0.0107	0.0977	0.0820	5.9000e-004		7.4200e-003	7.4200e-003		7.4200e-003	7.4200e-003		117.1959	117.1959	2.2500e-003	2.1500e-003	117.8923
NaturalGas Unmitigated	0.0107	0.0977	0.0820	5.9000e-004		7.4200e-003	7.4200e-003		7.4200e-003	7.4200e-003		117.1959	117.1959	2.2500e-003	2.1500e-003	117.8923

1231-1235 S Brand Blvd (Honda) - Los Angeles-South Coast County, Winter

EMFAC Off-Model Adjustment Factors for Gasoline Light Duty Vehicle to Account for the SAFE Vehicle Rule Applied**5.2 Energy by Land Use - NaturalGas****Unmitigated**

	NaturalGas Use	ROG	NOx	CO	SO2	Fugitive PM10	Exhaust PM10	PM10 Total	Fugitive PM2.5	Exhaust PM2.5	PM2.5 Total	Bio- CO2	NBio- CO2	Total CO2	CH4	N2O	CO2e
Land Use	kBTU/yr	lb/day										lb/day					
Automobile Care Center	996.165	0.0107	0.0977	0.0820	5.9000e-004		7.4200e-003	7.4200e-003		7.4200e-003	7.4200e-003		117.1959	117.1959	2.2500e-003	2.1500e-003	117.8923
Enclosed Parking with Elevator	0	0.0000	0.0000	0.0000	0.0000		0.0000	0.0000		0.0000	0.0000		0.0000	0.0000	0.0000	0.0000	0.0000
Unenclosed Parking with Elevator	0	0.0000	0.0000	0.0000	0.0000		0.0000	0.0000		0.0000	0.0000		0.0000	0.0000	0.0000	0.0000	0.0000
Total		0.0107	0.0977	0.0820	5.9000e-004		7.4200e-003	7.4200e-003		7.4200e-003	7.4200e-003		117.1959	117.1959	2.2500e-003	2.1500e-003	117.8923

1231-1235 S Brand Blvd (Honda) - Los Angeles-South Coast County, Winter

EMFAC Off-Model Adjustment Factors for Gasoline Light Duty Vehicle to Account for the SAFE Vehicle Rule Applied**5.2 Energy by Land Use - NaturalGas****Mitigated**

	NaturalGas Use	ROG	NOx	CO	SO2	Fugitive PM10	Exhaust PM10	PM10 Total	Fugitive PM2.5	Exhaust PM2.5	PM2.5 Total	Bio- CO2	NBio- CO2	Total CO2	CH4	N2O	CO2e
Land Use	kBTU/yr	lb/day										lb/day					
Automobile Care Center	0.996165	0.0107	0.0977	0.0820	5.9000e-004		7.4200e-003	7.4200e-003		7.4200e-003	7.4200e-003		117.1959	117.1959	2.2500e-003	2.1500e-003	117.8923
Enclosed Parking with Elevator	0	0.0000	0.0000	0.0000	0.0000		0.0000	0.0000		0.0000	0.0000		0.0000	0.0000	0.0000	0.0000	0.0000
Unenclosed Parking with Elevator	0	0.0000	0.0000	0.0000	0.0000		0.0000	0.0000		0.0000	0.0000		0.0000	0.0000	0.0000	0.0000	0.0000
Total		0.0107	0.0977	0.0820	5.9000e-004		7.4200e-003	7.4200e-003		7.4200e-003	7.4200e-003		117.1959	117.1959	2.2500e-003	2.1500e-003	117.8923

6.0 Area Detail**6.1 Mitigation Measures Area**

1231-1235 S Brand Blvd (Honda) - Los Angeles-South Coast County, Winter

EMFAC Off-Model Adjustment Factors for Gasoline Light Duty Vehicle to Account for the SAFE Vehicle Rule Applied

	ROG	NOx	CO	SO2	Fugitive PM10	Exhaust PM10	PM10 Total	Fugitive PM2.5	Exhaust PM2.5	PM2.5 Total	Bio- CO2	NBio- CO2	Total CO2	CH4	N2O	CO2e
Category	lb/day										lb/day					
Mitigated	0.4648	6.0000e-005	7.0400e-003	0.0000		3.0000e-005	3.0000e-005		3.0000e-005	3.0000e-005		0.0151	0.0151	4.0000e-005		0.0161
Unmitigated	0.4648	6.0000e-005	7.0400e-003	0.0000		3.0000e-005	3.0000e-005		3.0000e-005	3.0000e-005		0.0151	0.0151	4.0000e-005		0.0161

6.2 Area by SubCategory**Unmitigated**

	ROG	NOx	CO	SO2	Fugitive PM10	Exhaust PM10	PM10 Total	Fugitive PM2.5	Exhaust PM2.5	PM2.5 Total	Bio- CO2	NBio- CO2	Total CO2	CH4	N2O	CO2e
SubCategory	lb/day										lb/day					
Architectural Coating	0.0535					0.0000	0.0000		0.0000	0.0000			0.0000			0.0000
Consumer Products	0.4106					0.0000	0.0000		0.0000	0.0000			0.0000			0.0000
Landscaping	6.5000e-004	6.0000e-005	7.0400e-003	0.0000		3.0000e-005	3.0000e-005		3.0000e-005	3.0000e-005		0.0151	0.0151	4.0000e-005		0.0161
Total	0.4648	6.0000e-005	7.0400e-003	0.0000		3.0000e-005	3.0000e-005		3.0000e-005	3.0000e-005		0.0151	0.0151	4.0000e-005		0.0161

1231-1235 S Brand Blvd (Honda) - Los Angeles-South Coast County, Winter

EMFAC Off-Model Adjustment Factors for Gasoline Light Duty Vehicle to Account for the SAFE Vehicle Rule Applied**6.2 Area by SubCategory****Mitigated**

	ROG	NOx	CO	SO2	Fugitive PM10	Exhaust PM10	PM10 Total	Fugitive PM2.5	Exhaust PM2.5	PM2.5 Total	Bio- CO2	NBio- CO2	Total CO2	CH4	N2O	CO2e
SubCategory	lb/day										lb/day					
Architectural Coating	0.0535					0.0000	0.0000		0.0000	0.0000			0.0000			0.0000
Consumer Products	0.4106					0.0000	0.0000		0.0000	0.0000			0.0000			0.0000
Landscaping	6.5000e-004	6.0000e-005	7.0400e-003	0.0000		3.0000e-005	3.0000e-005		3.0000e-005	3.0000e-005		0.0151	0.0151	4.0000e-005		0.0161
Total	0.4648	6.0000e-005	7.0400e-003	0.0000		3.0000e-005	3.0000e-005		3.0000e-005	3.0000e-005		0.0151	0.0151	4.0000e-005		0.0161

7.0 Water Detail**7.1 Mitigation Measures Water**

1231-1235 S Brand Blvd (Honda) - Los Angeles-South Coast County, Winter

EMFAC Off-Model Adjustment Factors for Gasoline Light Duty Vehicle to Account for the SAFE Vehicle Rule Applied**8.0 Waste Detail**

8.1 Mitigation Measures Waste**9.0 Operational Offroad**

Equipment Type	Number	Hours/Day	Days/Year	Horse Power	Load Factor	Fuel Type
----------------	--------	-----------	-----------	-------------	-------------	-----------

10.0 Stationary Equipment

Fire Pumps and Emergency Generators

Equipment Type	Number	Hours/Day	Hours/Year	Horse Power	Load Factor	Fuel Type
----------------	--------	-----------	------------	-------------	-------------	-----------

Boilers

Equipment Type	Number	Heat Input/Day	Heat Input/Year	Boiler Rating	Fuel Type
----------------	--------	----------------	-----------------	---------------	-----------

User Defined Equipment

Equipment Type	Number
----------------	--------

11.0 Vegetation
